

## 3.31 BACKFILL REQUIREMENTS

# Backfilling Requirements

Do not backfill a basement wall until –

- Concrete has cured at least 7 days
- Support for top of wall has been installed
- Flooring system is in place and anchored to wall
- Waterproofing materials installed
- Footing drainage line installed
- Backfill material should be free of construction debris, sharp objects, and large rocks
- Backfilling protective material is recommended to protect water proofing

